



Deep Holes with a Difference

Upgrading its deep-hole drilling capability made a positive difference in this shop's part processing, business strategy, and customer service.

BY MARK ALBERT

Leese & Co. is deeply involved in deep-hole drilling. Although the company's two locations in the Greensburg, Pennsylvania area (not far from Pittsburgh) are home to many machining processes at which it is highly qualified, deep-hole drilling has been an area of specialized expertise and confidence that sets it apart from other suppliers that might serve its customers. While many shops shy away from the challenges of deep-hole drilling, Leese & Co. has made it a mainstay in the range of capabilities needed to process a variety of demanding workpieces used in diverse applications.

Maintaining this diversity is a key part of this job shop's business strategy. "Getting tied too closely to one industry or one type of workpiece is limiting and risky," says company president and owner, Christian Klanica. "Plus, a healthy mix of parts and customer applications keeps our skills honed and makes work more interesting," he adds. However, the company has built a reputation as a top-notch supplier of custom heat sinks and chill blocks, all of which require high-

precision deep-hole drilling. "It's a niche in which we are particularly strong, but one of many manufacturing options we offer for precision machining in prototype or production quantities," Mr. Klanica says.

Because the company uses deep-hole drilling on a daily basis and was experiencing growth in orders for its line of custom chill blocks, upgrading its deep-hole technology became a priority in early 2013. The deep-hole drilling machine that had served the company well for 17 years was no longer able to provide the flexibility, efficiency and reliability the shop needed. As the company began investigating improved deep-hole drilling technology, the buying team was determined to keep an open mind.

This outlook led them to consider offerings from a newcomer to the U.S. market, Precihole Machine Tools, a machine tool builder based in Mumbai, India. "We were willing to take this company seriously because their U.S. importer, Absolute Machine Tools, takes this product line very seriously. That gave us a lot of confidence," Mr. Klanica says.

In October 2013, Leese purchased a XY GVN 25/1-100 deep-hole drilling machine, the first machine from this builder installed in the United States. This machine provided significant advantages very quickly upon installation. "We can point

Leese & Co. produces a line of custom chill blocks for the thermal management of drive transmissions and other applications. One of the most popular styles requires holes drilled lengthwise through a 12-inch by 5-inch block of copper alloy.

The majority of the CNC machines are in the original building, which is the larger of the two. The second building, occupied since 1996, contains sales and administrative offices, as well as an ample production area where the deep-hole drilling machines are located. A Mazak Nexus 4000-III HMC, the company's latest machining center acquisition, is also located here, directly across from the new deep-hole drilling machine. For the chill blocks and heat sinks, these two machines can be operated as a single cell with one operator. The older deep-hole machine has been moved to the back of this shop area and is occasionally called into service for utility purposes.

DEPTH AT THE SOURCES

Precihole may be new to the United States, but it is not new to production of hole finishing and deep-hole drilling machines. The company has been providing such machines to India, South America, Europe and Asia for more than 25 years. Its products include deep hole drilling equipment (single- and three-axis gun drilling machines, BTA/STS drilling machines and bore-trepanning machines), hole finishing equipment (skiving, honing, reaming and lapping machines) and rifling machines (button rifling and cut rifling models).

Absolute Machine Tools (Lorain, Ohio) was

appointed the exclusive importer for Precihole in July 2013. One of the most successful machine tool importers in the country, Absolute now represents a range of brands and machine types. Because it recognizes the importance of a U.S.-based staff to handle application engineering, service, customer support, training and preventive maintenance programs, Absolute was a good fit for Precihole as a leading Indian machine tool builder entering the U.S. market.

Mr. Klanica admits having concerns about purchasing an overseas machine with no established U.S. user base. These concerns were allayed by three factors, he says. The overall construction, fit and finish of the deep-hole machine compared favorably to other top-of-the-line machines from globally active builders. Likewise, many of the major components of the machine were from well-known U.S. or European suppliers, including Baldor for pump motors, Siemens for the CNC unit, SKF for bearings, Bijur the for lubrication system and Mayfran for the chip conveyor. Finally, the sales and service support from the importer were characterized by experience, professionalism and responsiveness.

EARLY RESULTS

Mr. Klanica reports that the new machine was installed in one day and running at full capacity



Shop owner Chris Klanica (left) and machinist Tim Wolf review programs for jobs scheduled to run on the deep-hole machine. The Siemens 828D control enables shopfloor programming of three-axis work, including automated routines for bolt hole circles and other patterns.



Adjustable supports inside the machine optimize the positioning of bushings for smooth, straight Z-axis feed of drills as long as 39 inches. When running, the machine enclosure keeps the high pressure (1000 psi) coolant contained for clean, safe operation.


within a week. "We expected the machine to reflect the fact that deep-hole drilling technology in general has made the kind of strides in productivity and quality that are apparent in other metal-working processes. But this model in particular proved to be especially well-suited to our needs," he says.

Some of the general aspects of deep-hole technology that make this process part of a new era include higher torque spindle motors, more powerful CNC features, better enclosures for cleaner operation and more efficient coolant delivery and filtering. Some of the features that

distinguish the new machine at Leese include faster and simpler programming at the machine for a lower learning curve for operators, retention of position coordinates in the event of a power disruption, a collet system that enables shorter setups and an internal load meter that stops the machine before tool wear can result in breakage, among other features.

The tool load monitoring system proved to be especially important. Concern about tool breakage forced the shop to be overly cautious and conservative in feeds and speeds with the older technology. Now drills can be used at more appropriate and productive parameters with safety. This enables the machine to take full advantage of its high-torque capability. That load meter monitors the current drawn by the drilling spindle. If the current draw (amperage) reaches a predetermined level, the machine detects the change and shuts down automatically to prevent damage to the tool or the workpiece. The threshold for machine shutdown can be programmed into the CNC logic, and the feedback is continu-

Engineers at the machine tool builder's factory worked with Leese to design and construct this custom workholding fixture. This fixturing strategy enhances the productivity derived from faster drilling rates.





ously shown on the control screen.

The more precise control of the drilling process and the stability of the machine structure also enable the shop to use off-the-shelf deep hole drills, rather than tools with custom-ground tip angles on cutting edges that were tweaked for optimal performance on the older machine. On the new machine, standard drills can outperform the custom tooling formerly used by a factor of 3.5, and the shop expects the productivity gain to reach a four-fold improvement as it gains experience with parameter settings. The shop has used drills with diameters from 0.1 to 0.75 inch in diameter.

Initial results with new deep-hole drilling technology were impressive. For example, when drilling a copper part with five 12-inch holes, the shop saves 33.3 minutes of machine time. Whereas the older technology drilled these holes at 0.6 ipm, the new technology drills them at 0.9 ipm. With the older machine, a 12-inch hole in copper could be drilled in 20 minutes. With the new machine, that whole can be drilled in 12.33 minutes.


Given an average of 48 copper chill blocks per order, the new machine enables 26.66 hours to be saved per order, a 30-percent reduction in

The deep-hole machine was installed next to an HMC equipped with a pallet changer. The two new machines can be used together as a cell to produce the chill blocks.

machine time. Although the shop has processed fewer steel parts on the new machine so far, similar improvements have been recorded. For example, a hole in steel was formally drilled at 0.7 ipm. The new real rate is 1.5 ipm. With more experience and a strong continuous improvement culture, further improvements are expected to be forthcoming.

PROCESSES CHANGES

Mr. Martz attributes additional productivity gains to the engineering input from Precihole's factory. For example, it designed and built a custom fixture that enables work pieces to be set up in multiple gangs of three so that three pieces can be completed in one cycle before indexing. (The X-Y table provides precise positioning for processing of multiple part setups as well as prismatic workpieces). This capability had been demonstrated with prototype parts prior to purchase. "We could anticipate and prepare for these results. It also helped to streamline the training process,"



The copper workpieces make two passes on the HMC—one before and one after the lengthwise holes are drilled. Vises on the pallet-mounted upright secure the workpieces for both operations.

Because the deep holes produced by the Precihole machine consistently hold tight tolerances for straightness, size and location, the results complement the accuracy of operations on the HMC.

FLEXIBILITY RUNS DEEP

Although custom heat sinks and chill blocks provide the most striking examples of how advanced deep-hole drilling technology has benefited this shop, they don't tell the whole story. "CNC control of the X-Y table makes it a very flexible machine for hole making operations on prismatic parts, whether or not the holes can be technically classified as deep ones," Mr. Klanica explains.

For example, he says the machine is ideal for producing bolt hole circles or other hole patterns on the ends of long workpieces that would be difficult to process on standard machining centers. This flexibility enables the shop to drill bolt hole circles on the ends of aluminum spool valves for hydraulic applications. The spools required a 5.63-inch diameter circle of six evenly spaced holes 0.625 inch in diameter. A similar application called for a pattern of fastener holes on the ends of long steel axle assemblies for railcars. Typically, the shop uses the same carbide-tipped drills and low-viscosity mineral oil coolant for "non-deep" hole-making operations.

Leese has used the new machine to produce coolant lines in steel mold bases, to drill lubrication holes for grease to reach bearing races deep within rotational assemblies, and many other applications.

Today's deep-hole drilling technology has the capability and flexibility to make it a mainstay for the diverse applications found in a broad-spectrum manufacturing company such as Leese. "We need specialized equipment for deep-hole drilling, and we have the skills to make it one of our specialties," Mr. Klanica says. "But we use it so much that it has become an ordinary part of what we consider extraordinary service for our customers." ■

Mr. Martz recalls.

An important benefit of previewing machining results and evaluating the custom fixture and was an insight into a basic process change involving the nearby HMC. The shop implemented a two-step process whereby the chill blocks are clamped two by two in vises mounted on tombstones carried by the pallet changer. In this first step, the blocks are squared with a face mill, and then moved to the fixture on the deep-hole machine. After the lengthwise holes are completed, the blocks return to the HMC, where they are remounted in the same vises.

In the second step at the HMC, cross holes are drilled through the side of the blocks. Once this step is completed, plugs are welded into the appropriate side holes to form one continuous channel inside the block, thus enabling it to circulate fluid internally to remove heat in end-user applications such as marine drive transmissions.

For more about Precihole hole drilling machines, call 800-852-7825 or visit absolutemachine.com.